

## CONTROL TECHNOLOGY



Test facilities in accordance with EN 12589: control tolerance; control response; pressure loss; characteristics for various upstream conditions; master-slave, etc.

Other possible measurements:

- Leakage test according to EN 1751 (dampers, housings). A test rig has been set up in the Anholt plant for leakage testing in accordance with EN 1751. Part of our series production is tested here.
- Testing of mixing boxes (e.g. degree of mixing efficiency)
- Testing of decentralised ventilation units (volume flow rates; suction / pressure characteristics, etc. according to VDMA 24390)